



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2010
(Projected water availability in the absence of Monticello Dam)

Reach No. 4: Hwy. 180 Bridge to Mace Boulevard Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,118	599	154	71	28	8	48
10%	1,265	408	123	55	10	0	16
15%	914	321	97	38	3	0	2
20%	813	230	84	31	0	0	0
25%	606	184	72	20	0	0	0
30%	483	172	57	7	0	0	0
35%	411	147	46	0	0	0	0
40%	352	130	41	0	0	0	0
45%	285	123	36	0	0	0	0
50%	256	115	31	0	0	0	0
55%	227	90	22	0	0	0	0
60%	201	79	8	0	0	0	0
65%	183	66	1	0	0	0	0
70%	160	55	0	0	0	0	0
75%	140	51	0	0	0	0	0
80%	115	36	0	0	0	0	0
85%	82	29	0	0	0	0	0
90%	68	12	0	0	0	0	0
95%	46	6	0	0	0	0	0
100%	0	0	0	0	0	0	0