



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2012
(Projected water availability in the absence of Monticello Dam)

Reach No. 5: Mace Blvd. Bridge to River Mile 0.0 of Putah Creek

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,097	593	184	74	24	11	53
10%	1,268	411	127	58	5	2	27
15%	928	320	100	43	0	0	9
20%	831	245	83	33	0	0	0
25%	651	201	71	23	0	0	0
30%	494	181	54	10	0	0	0
35%	423	158	44	1	0	0	0
40%	368	140	39	0	0	0	0
45%	296	130	33	0	0	0	0
50%	260	124	28	0	0	0	0
55%	233	100	21	0	0	0	0
60%	204	87	7	0	0	0	0
65%	187	75	0	0	0	0	0
70%	163	62	0	0	0	0	0
75%	148	58	0	0	0	0	0
80%	118	44	0	0	0	0	0
85%	85	38	0	0	0	0	0
90%	71	20	0	0	0	0	0
95%	49	13	0	0	0	0	0
100%	0	0	0	0	0	0	0