



# Solano County Water Agency

**Lower Putah Creek Riparian Water Availability Forecast: May 1, 2018**  
*(Projected water availability in the absence of Monticello Dam)*

**Reach No. 4: Hwy. 180 Bridge to Mace Boulevard Bridge**

**Average Monthly Flow in Cubic Feet Per Second (cfs)**  
*(projected stream flow at downstream end of reach)*

<b>Percent Exceedance</b>	<b>Apr</b>	<b>May</b>	<b>Jun</b>	<b>Jul</b>	<b>Aug</b>	<b>Sep</b>	<b>Oct</b>
5%	NA	569	174	85	22	29	71
10%	NA	422	132	74	0	21	53
15%	NA	347	106	68	0	17	32
20%	NA	270	98	57	0	13	25
25%	NA	227	86	49	0	10	21
30%	NA	210	73	39	0	8	16
35%	NA	188	64	28	0	7	13
40%	NA	174	59	22	0	5	13
45%	NA	163	55	20	0	3	13
50%	NA	157	50	17	0	2	13
55%	NA	132	42	15	0	2	13
60%	NA	120	32	13	0	2	13
65%	NA	108	23	10	0	2	13
70%	NA	97	17	10	0	2	13
75%	NA	94	15	10	0	2	13
80%	NA	81	9	10	0	2	13
85%	NA	74	3	10	0	2	13
90%	NA	55	3	10	0	2	13
95%	NA	49	3	10	0	2	13
100%	NA	30	3	10	0	2	13