



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: May 1, 2020
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	NA	546	181	83	56	23	63
10%	NA	411	142	73	32	14	48
15%	NA	333	116	66	26	11	25
20%	NA	265	109	56	19	6	15
25%	NA	220	97	47	15	4	12
30%	NA	201	85	36	11	2	7
35%	NA	180	75	27	8	1	7
40%	NA	165	71	21	7	0	7
45%	NA	154	67	18	6	0	7
50%	NA	148	61	16	6	0	7
55%	NA	122	54	14	6	0	7
60%	NA	110	44	12	6	0	7
65%	NA	99	35	10	6	0	7
70%	NA	88	29	10	6	0	7
75%	NA	84	27	10	6	0	7
80%	NA	73	23	10	6	0	7
85%	NA	66	16	10	6	0	7
90%	NA	46	14	10	6	0	7
95%	NA	40	14	10	6	0	7
100%	NA	21	14	10	6	0	7