



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2022
(Projected water availability in the absence of Monticello Dam)

Reach No. 1: Putah Diversion Dam to Hwy. 505 Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,001	519	177	80	52	25	78
10%	1,233	391	136	68	27	14	42
15%	946	314	110	58	20	9	19
20%	828	242	101	48	13	4	7
25%	699	197	88	38	8	1	4
30%	528	179	75	26	4	0	0
35%	459	156	64	17	1	0	0
40%	394	141	59	11	0	0	0
45%	328	130	54	8	0	0	0
50%	299	123	49	5	0	0	0
55%	266	98	39	3	0	0	0
60%	231	87	29	1	0	0	0
65%	218	75	20	0	0	0	0
70%	189	64	15	0	0	0	0
75%	168	59	13	0	0	0	0
80%	142	46	7	0	0	0	0
85%	111	37	1	0	0	0	0
90%	93	22	0	0	0	0	0
95%	65	15	0	0	0	0	0
100%	22	0	0	0	0	0	0