



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2022
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,026	551	203	99	65	26	90
10%	1,252	416	156	82	35	11	50
15%	962	336	127	71	27	6	25
20%	840	260	116	59	18	0	12
25%	710	214	101	48	13	0	8
30%	536	193	86	34	7	0	3
35%	465	168	74	25	4	0	2
40%	398	151	67	18	2	0	1
45%	331	139	62	15	1	0	1
50%	302	130	55	11	1	0	0
55%	268	104	46	9	0	0	0
60%	232	92	34	6	0	0	0
65%	218	79	25	5	0	0	0
70%	188	68	19	4	0	0	0
75%	166	61	17	4	0	0	0
80%	139	48	10	3	0	0	0
85%	107	39	4	3	0	0	0
90%	90	22	2	3	0	0	0
95%	61	15	2	3	0	0	0
100%	17	0	2	3	0	0	0