



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2023
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	1,974	522	176	78	52	20	75
10%	1,210	398	138	66	27	9	42
15%	930	320	112	56	20	5	18
20%	805	246	104	46	12	0	7
25%	685	200	89	36	7	0	3
30%	509	183	77	23	3	0	0
35%	437	158	67	14	0	0	0
40%	380	142	61	9	0	0	0
45%	310	134	56	6	0	0	0
50%	283	125	51	3	0	0	0
55%	251	100	41	1	0	0	0
60%	218	89	30	0	0	0	0
65%	199	77	22	0	0	0	0
70%	176	64	18	0	0	0	0
75%	151	59	15	0	0	0	0
80%	126	48	9	0	0	0	0
85%	97	37	4	0	0	0	0
90%	76	23	1	0	0	0	0
95%	53	13	0	0	0	0	0
100%	9	0	0	0	0	0	0